



32 ELM STREET, GOFFSTOWN, NH 03045  
497-3200



## **STANDARD PRE-PACKAGED AUTOMATIC STANDBY INSTALLATION**

- SITE REVIEW.
- DELIVERY OF GENERATOR AND TRANSFER SWITCH TO YOUR HOME.
- PEA STONE BASE WITH 2X4 PRESSURE TREATED FRAME, PREPARED ON YOUR PRE-LEVELLED GROUND.
- GENERATOR INSTALLED ON PEA STONE BASE, GENERATOR LOCATED WITHIN 4 FEET OF HOME. STARTING BATTERY INSTALLED. GROUND ROD INSTALLED AND GENERATOR ATTACHED TO GROUND ROD WITH #2 BARE STRANDED COPPER.
- TRANSFER SWITCH INSTALLED BY A MASTER ELECTRICIAN IN YOUR BASEMENT OR GARAGE WITHIN ONE FOOT OF MAIN ELECTRICAL PANEL AND WITHIN 30 FEET OF GENERATOR. SELECTED CIRCUITS ARE WIRED TO TRANSFER SWITCH.
- GENERATOR STARTUP AND TESTING OF PROPER OPERATION DONE AFTER GAS PROVIDER HAS CONNECTED UNIT
- NOTE: GAS CONNECTION IS NOT INCLUDED IN THIS INSTALLATION.  
FYI.....Required fuel pressure for air cooled generators - 5" to 7" of water column for natural gas, 11" to 14" of water column for LP gas.
- ALL DST ELECTRIC INSTALLATION SERVICES GUARANTEED BY OUR 1 YEAR LABOR WARRANTY.